

NOTE: CONTRACTOR SHALL OPERATE AND TRANSFER SEWAGE TREATMENT PLANT OF 18 MLD CAPACITY TO TREAT THE PREDOMINANTLY DOMESTIC RAW SEWAGE AND SEPTAGE TO THE GUARANTEED EFFLUENT CHARACTERISTICS BOD<10 MGL, COD<50MGL, TSS<10 MGL, TOTAL NITROGEN < 2 MG/L, NH4N<5MG/L TOTAL PHOSPHOROUS < 2 MG/L, FECAL COLIFORM<230 MPN/100 ML AND ALL ALLIED INFRASTRUCTURE INCLUDING SUPPLY, INSTALLATION OF PUMPING PLANTS IN PUMPING STATION, 02 Nos. NALA TAPPING ARRANGEMENT & LAYING OF SEWER LINE FROM NALAS TO S.T.P. ETC. WITH OPERATION & MAINTENANCE PERIOD OF 5 YEARS IN KASHIPUR TOWN OF DISTT. UDHAM SINGH NAGAR, STATE OF UTTARAKHAND, INDIA UNDER AMRUT

Contract No: 

Contract No:

Name of the Bidder/ Bidding Firm/ Company : SN ENVIRO-TECH PVT. LTD.

PRICE SCHEDULE


(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	RATE (with all Taxes) In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Rs. P	TOTAL AMOUNT In Words	TEXT #
1	2	4	5	6	7	8	
1.00	Price Schedule : Part A Design Build etc. work for construction of 18 MLD SPS & STP						



DOCUMENT PROCESS DESIGN ENGINEERING AND DRAWINGS :-
 Process & Instrumentation Diagrams, Flow Charts, Hydraulic Diagram and Complete Process Design, Site Layout Plan and Site Grading Plan, Single line Diagrams, Control Philosophy & Basic Electrical and Instrumentation Drawings, Preparation of "QA" and construction procedure manual along with "Test Plan", Civil and Mechanical General Arrangement Drawings, Architectural Drawings, Structural Designs and Drawings and Construction Drawings, Mechanical and Piping data sheets and Drawings, Detailed Electrical and Instrumentation and control Systems, Drawings and datasheets including PLC and SCADA, Ancillary Works and Non-Technology Structural Drawings including roads and drainage and compound wall bypass + treated effluent disposal arrangement like pipe line etc, RCC drain, external electrification plans, As-Built Drawings, Operation and Maintenance Manuals and Training Program and Manuals, etc. complete (To be submitted in 6 Nos. sets).

Break-up of works of item No. 1.01 as follows :- Break-up of works of item No. 1.01 as follows :-

1.02		1 000 Job -	152500000.00	152500000.00	INR Fifteen Crore Twenty Five Lakh Only
	<p>Civil and Structural Works: Construction of 18 MLD SPS & STP Includes all civil works such as Site Development & Infrastructure Works including site Cleaning / Grading / Levelling and Reclamation Compound Wall with Gates as shown in Drawings, Roads along boundary all as shown in site plan, bypass + treated effluent pipe as shown in site plan, Internal Roads & Pathways, Internal Sewerage Network and Internal Storm Water Drains, Landscaping and Gardening, Piping & Valves, all Liquid Retaining Structures (Such as receiving chamber coarse and fine screen channels, grit chambers) and other liquid retaining as required in treatment technology proposed by bidder and as specified in bid document) It also includes others various Buildings / Sheds such as administration cum MCC and Control Building, building for E&M equipment as per norms / practice and sample testing laboratory complete with equipments etc. disposal of bypass sewage to laxmpur minor drain & Kalash Mandap Drain disposal of treated effluent to laxmpur minor drain & Kalash Mandap Drain for irrigation as shown in site plan, piping between different units of STP complete in all respect as specified in bid document</p>				

Date: 12/12/2023

Sl. No.	Part B Nallah Tapping Works at Laxmipur Minor Drain & Kalash Mandap Nallah including all allied works	Job	Quantity	Rate	Amount	Total
2.01	<p>Design, development, supply of equipment, erection of equipment, civil, electro mechanical and instrumentation control works, including testing, commissioning of Nallah Tapping Works at Laxmipur Minor Drain & Kalash Mandap Nallah including all allied works as per specification given in bid document. PROCESS DESIGN ENGINEERING AND DRAWINGS :- Process & Instrumentation Diagrams, Flow Charts, Hydraulic Diagram and Complete Process Design, Site Layout Plan and Site Grading Plan, Single line Diagrams, Basic Electrical and Instrumentation Drawings, Preparation of "QA" and construction procedure manual along with "Test Plan", Civil and Mechanical General Arrangement Drawings, Structural Designs and Drawings and Construction Drawings, Mechanical and Piping data sheets and Drawings, Detailed Electrical and Instrumentation and control Systems, Drawings and datasheets, Ancillary Works and Non-Technology Structural Drawings including roads and drainage and compound wall sewer line & pipe line external electrification plans, As-Built Drawings, Operation and Maintenance Manuals and Training Program and Manuals, etc. complete (To be submitted in 6 Nos. sets). Break-up of works of item No. 2.01 as follows :-</p>					
2.02	Civil and Structural Works: Liquid Retaining Structures including: as specified in bid document	1,000 Job		425000.00	425000.00	INR Four Lakh Twenty Five Thousand Only
2.03	Weir Gate (2 Nos.)	1,000 Job		700000.00	700000.00	INR Seven Lakh Only
2.04	Trash Screen Channels (2 Nos.) (1W+1SB)	1,000 Job		3500000.00	3500000.00	INR Thirty Five Lakh Only
2.05	Siltng Trap (2 Nos) (1W+1SB)	1,000 Job		9100000.00	9100000.00	INR Ninety One Lakh Only

[Handwritten Signature]

[Handwritten Signature]

